
SHORTFALL IN COMMISSIONING OF BOILER

As a Commissioning professional, lot of unexpected things are experienced during the Commissioning of Boiler, which are never recorded but leave behind a great impact in terms of performance, money and failures.

Commissioning takes own time without bypassing the events, but there is always shortage of time from both end i.e. SELLER & PURCHASER. This shortage of time is always beneficial to SELLER as anyhow activity is completed.

Commissioning of Boiler require a systematic approach in a planned & recorded way to start plant in a perfect manner. Actually, there is a normal tendency to neglect the systematic & sequential approach during commissioning on behalf of urgency.

Defects Noticed during & after Commissioning of Boiler:-

- a) Piping Supports misalignment & uneven loading in hot condition
- b) Shifting of Piping / Piping Support from its original position
- c) Water carryover in PRDS piping after de-superheating section
- d) High Spray water flow to control Main Steam temperature
- e) Uneven Thermal Expansion of Pressure Parts / Casing
- f) Abnormal Vibration in Pressure Parts / Casing / Ducting
- g) Heavy Fluctuation in Drum level, Furnace Draft
- h) High back end temperature (Flue Gas Temperature at APH Outlet)
- i) Maximum Loading of Fans & Blowers
- j) High Emission/SPM from ESP / Bag Filter
- k) High Un-burnt Carbon in Fly Ash / Bottom Ash
- l) Inadequate drain piping of PRDS, Soot Blowers, Control Stations
- m) Secondary Combustion in Superheater Zone
- n) Bed Material slippage in Wind box / Bed material shifting on grid floor
- o) Water carryover from Deaerator Air/Gas Vents
- p) Water ingress in Insulation
- q) Improper fixing of Insulation & Cladding
- r) High insulation cladding surface temperature w.r.t. design
- s) High sound decibel from equipments / silencer
- t) High Auxiliary Power Consumption w.r.t. individual equipment
- u) Less Difference of Pressure in-between Steam Drum & Boiler Feed pump discharge to adjust power consumption
- v) No Approach for Valves, Dampers, Instruments, O&M Work
- w) Non availability of Inter-connecting platform, Safe working platform

Mandatory steps for commissioning of Boiler:-

(Under mentioned steps are bypassed / clubbed with each other to reduce time span/unavailability of resources and inputs/incompetent personnel/low priority client)

1) Pre Commissioning

- a) Mechanical completion protocol from Erection
- b) Electrical system completion protocol from Erection
- c) Instrumentation completion protocol from Erection
- d) Refractory application completion protocol
- e) Installation of Equipments, Vessels, Tank w.r.t. drawing / protocol
- f) Pressure parts protocol
- g) Hydraulic Test Protocol
- h) Non Pressure Parts protocol
- i) Supporting of Piping & Ducting w.r.t. drawing / protocol
- j) Routing of IBR, Non-IBR piping w.r.t. drawing/ protocol
- k) Buck stay & Seismic support w.r.t. drawing/ protocol
- l) Installation of System & Instrumentation w.r.t. P&ID
- m) FAT report for Control, Interlock, Protection & Safety systems / Logics / Trip and Alarm Values
- n) Availability of Commissioning Inputs like Air-Water-Fuel, Spares & Tools, Documents
- o) Thermal Expansion Drawing & Details
- p) Safe Approach / Platform for Operation with proper illumination
- q) Training/Discussion with O&M team before start of commissioning activity

2) Cold commissioning

- a) Flushing – Oil, Water, Air with temporary circuit
- b) Cleaning – Manual, Water, Air
- c) Lubrication
- d) Gasket & Joints
- e) Commissioning Inputs – Specification/Details/Test Reports
- f) Loop continuity, Loop testing, DCS / PLC / SCADA system startup
- g) Checking & Testing (SAT) for Control, Interlock, Protection & Safety systems / Logics / Values
- h) List of Instruments w.r.t. individual P&ID for setting, calibration & testing
- i) List of IBR & Non IBR Piping Supports for setting
- j) List of Ducting Supports for setting
- k) List of Expansion Bellow / Expansion Joint for checking
- l) List of Motors, MCC Panel, setting & testing & trial run at No load
- m) List of Equipments, checking & testing & trial run
- n) List of Tank & Vessels, checking
- o) Temporary Steam blowing line arrangement for Boiler, PRS & PRDS
- p) Blow down water drain trench arrangement
- q) Air Leak test of Air circuit (minimum +100 mmwc)
- r) Gas leak test of Gas circuit, ESP/Bag Filter casing (minimum +100 mmwc)
- s) Short Circuit test for Air Pre-heater (APH)
- t) Thermal Expansion provision checking & Fixing of measuring indicator
- u) Insulation & Cladding completion

3) Hot Commissioning

- a) Hydraulic Test of Boiler before start of Hot Commissioning
- b) Cold setting of Safety Valves & removal of Hydro test Plug
- c) Refractory Dry Out
- d) Cleaning/Checking of Blow down tanks
- e) Acid Cleaning / Alkali Boil Out
- f) Pressure Boil Out
- g) Header Internal Inspection (Furnace, Economizer)
- h) Steam Drum Internal Inspection, Refractory Inspection
- i) Steam Blowing
- j) Safety Valve Floating & Setting
- k) Boiler Part Load Operation & Control Tuning
- l) PRS & PRDS Steam Blowing
- m) PRS & PRDS Commissioning & Control Tuning
- n) Deaerator Charging & Control Tuning
- o) Boiler Water Chemistry analysis & testing of Control parameters
- p) Comparison with Predicted parameters at Part Load Operation of Boiler
- q) All equipments history sheet & parameter control
- r) Boiler Full Load Operation & Control Tuning
- s) Comparison with Predicted parameters at Full Load Operation of Boiler
- t) Steam Test as per IBR Norms
- u) Boiler Overload Trial Operation for specific duration
- v) Comparison with Predicted parameters at Over Load Operation of Boiler
- w) Handover of Drawings / Boiler Technical Details / Test Reports / Protocols / Equipments Manual / Test Certificates / Instrument Calibration Certificate / Electrical related documents / Performance Curve / Correction Curve / Performance Procedure etc
- x) Boiler Reliability Run Test
- y) Individual Equipments Performance test trial
- z) Boiler Performance Test Trial
- aa) As built drawings / documents for changes done during commissioning stage & performance trial run
- bb) Boiler Performance Guarantee Test
- cc) Handover of mandatory spares, tools as per contract
- dd) Project closing report for major activities/mile stones with troubleshooting/modification implemented

M/s Unite Energy Corporation LLP is keen to provide the Spares, Sales & Services, Retrofit & Site Repairs, Consultancy & troubleshooting support to mitigate the irregularities in the plant, minimize breakdown & downtime and improvise design & system performance to improve the overall plant's health and performance.

Regards

Pramesh Kumar Jain

Chief Executive- Technical

Mb +91 9868499319

pramesh.uniteenergy@gmail.com